

**100 N. Broadway
Red Oak, IA 51566**

Estimate

Date:	Estimate #
10/24/2023	4091397

Name / Address:

Clarinda Community School District
423 East Nodaway
Clarinda, IA 51632



Everlasting Customer Relationships

Office: (712)623-5558
ajones@jonesmechanicalinc.com
www.jonesmechanicalinc.com

Terms	Rep
Net 30	AJ

Item	Description	Qty	Total:
	Installation of 9 Climate Master water source heat pumps. Transition to existing supply and return duct to complete tie in. Reuse existing condensate drain line and reroute to new WSHP. Adapt to existing building loop supply and return piping to complete tie in to new WSHP. Existing electrical disconnects to be reused. Flexible conduit from disconnects to be installed and rerouted to new WSHP as needed. Existing BAS controls to be reinstalled if online and functional. If BAS is offline 24-volt thermostat to be installed using pvc conduit and 2 x 4 box located in the area that unit serves.		
15 HVAC	#102 3.5 ton Horizontal Tranquility Compact 460/60/3 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Left Return and Back Discharge w/ PSC Motor equipment / materials		5,561.00
15 HVAC	labor		8,064.00
15 HVAC	#128 1.5 ton Horizontal Tranquility Compact 265/60/1 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Left Return and Straight-Thru Discharge w/ PSC Motor equipment / materials		4,770.00
15 HVAC	labor		5,376.00
	#131 1 ton Horizontal Tranquility Compact 265/60/1 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Left Return and Straight-Thru Discharge w/ PSC Motor		

Total

**This price may be reviewed if
not accepted within 30 days.
We look forward to working
with you on this project!**

Purchaser's Acceptance: _____

Jones Mechanical, Inc Rep: _____

**100 N. Broadway
Red Oak, IA 51566**

Estimate

Date:	Estimate #
10/24/2023	4091397

Name / Address:

Clarinda Community School District
423 East Nodaway
Clarinda, IA 51632



Everlasting Customer Relationships

**Office: (712)623-5558
ajones@jonesmechanicalinc.com
www.jonesmechanicalinc.com**

Terms	Rep
Net 30	AJ

Item	Description	Qty	Total:
15 HVAC 15 HVAC	equipment / materials labor		4,186.00 5,376.00
15 HVAC 15 HVAC	#308 2 ton Horizontal Tranquility Compact 265/60/1 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Right Return and Strait-Thru Discharge w/ PSC motor equipment / materials labor		4,868.00 5,376.00
15 HVAC 15 HVAC	#E408 10 ton Vertical Tranquility Compact 460/60/3 Voltage, DXM2 Controls, 2" Filter Frame, Standard Motor w/ Standard RPM, Copper Coil, Back Return and Top Discharge equipment / materials labor		17,949.00 9,140.00
15 HVAC 15 HVAC	#W408 10 ton Vertical Tranquility Compact 460/60/3 Voltage, DXM2 Controls, 2" Filter Frame, Standard Motor w/ Standard RPM, Copper Coil, Back Return and Top Discharge equipment / materials labor		17,949.00 9,140.00
15 HVAC 15 HVAC	#428 1 ton Horizontal Tranquility Compact 265/60/1 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Left Return and Back Discharge w/ PSC Motor equipment / materials labor		4,186.00 5,376.00

Total

**This price may be reviewed if
not accepted within 30 days.
We look forward to working
with you on this project!**

Purchaser's Acceptance: _____

Jones Mechanical, Inc Rep: _____

**100 N. Broadway
Red Oak, IA 51566**

Estimate

Date:	Estimate #
10/24/2023	4091397

Name / Address:

Clarinda Community School District
423 East Nodaway
Clarinda, IA 51632



Everlasting Customer Relationships

**Office: (712)623-5558
ajones@jonesmechanicalinc.com
www.jonesmechanicalinc.com**

Terms	Rep
Net 30	AJ

Item	Description	Qty	Total:
15 HVAC	#438 1.5 ton Horizontal Tranquility Compact 265/60/1 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Left Return and Straight-Thru Discharge w/ PSC Motor equipment / materials		4,770.00
15 HVAC	labor		5,376.00
15 HVAC	#439 2 ton Horizontal Tranquility Compact 265/60/1 Voltage, DXM2 Controls, 1" Filter Rail, Copper Coil, Left Return and Straight Thru Discharge w/ PSC Motor equipment / materials		4,870.00
15 HVAC	labor		5,376.00
15 HVAC	Estimated freight		1,376.00
	Lead time on equipment 3.5 ton and less 5 to 7 weeks. Lead time on 10 ton equipment 10 to 12 weeks		
	Exclusions: Ceiling tile / grid removal and replacement.		

Total **\$129,085.00**

**This price may be reviewed if
not accepted within 30 days.
We look forward to working
with you on this project!**

Purchaser's Acceptance: _____

Jones Mechanical, Inc Rep: _____